

**PLANNING AND DEVELOPMENT SERVICES – BUILDING INSPECTION****INSPECTION GUIDELINES:  
GREEN BUILDING – NON-RESIDENTIAL PRE-CONSTRUCTION MEETING****INSPECTION CODE:** 151**SCOPE:** NON-RESIDENTIAL**APPLICABLE CODES:** 2019 CBC, CRC, CPC, CMC, CEC, CALGreen, CEnC, and PAMC

*The information provided in this document is general and intended as a guide only. Each project is unique and additional requirements may be enforced as deemed appropriate.*

**NON-RESIDENTIAL PROJECTS**

- The Green Building Pre-Construction Meeting, Inspection 151, is required for all projects that triggered Mandatory, Tier 1, or Tier 2 requirements during the plan review process. For information regarding these triggers, please see the “Green Building Special Inspectors and Project Triggers” inspection checklist.

**CALGREEN MANDATORY PROJECTS****ITEMS OF DISCUSSION DURING GREEN BUILDING PRE-CONSTRUCTION MEETING**

- During the Green Building Pre-Construction inspection, the general contractor and the City of Palo Alto (CPA) Building Inspector shall:
  - Review the “GB-1” sheet in the approved set of plans and the “Green Building GB-1 Sheet Submittals” checklist.
  - Provide an overview of the requirements applicable to the project and confirm if the project triggered only Mandatory requirements. If it found that the project triggers Tier 1 requirements, a revision will be required (refer to the “Green Building Common Errors” inspection checklist for information on how to get a revision).
  - Review the Green Building inspection checklist, sequence of inspections, and discuss compliance expectations throughout construction.
  - Review importance of maintaining paperwork to prevent delays in the successful completion of the inspections that follow.
  - Review resources available to the construction team and go over any questions and answers.

**REQUIRED ITEMS DURING CALGREEN MANDATORY INSPECTION 151**

- The items that follow shall be complete at the time when Inspection 151 is scheduled to ensure that the CPA Building Inspector signs off the inspection card.
  - Storm water drainage and retention during construction
  - Local storm water pollution prevention
  - Best management practices
  - Exterior noise transmission
  - Interior sound transmission

**CALGREEN TIER 1 AND TIER 2 PROJECTS**

- For Tier 1 and Tier 2 projects, the contractor shall coordinate the Green Building Pre-Construction Meeting with the general contractor, Green Building Special Inspector (GBSI), and the City of Palo Alto Building Inspector. The GBSI shall be physically present and shall lead the meeting.

**ITEMS OF DISCUSSION DURING GREEN BUILDING PRE-CONSTRUCTION MEETING**

- During the Green Building Pre-Construction inspection, the general contractor, the GBSI and the City of Palo Alto (CPA) Building Inspector shall:
  - Review the “GB-1” sheet in the approved set of plans and the “Green Building GB-1 Sheet Submittals” checklist.
  - Provide an overview of the requirements applicable to the project.
  - Review the Green Building inspection checklist, sequence of inspections, and discuss compliance expectations throughout construction.
  - Review importance of maintaining paperwork to prevent delays in the successful completion of the Green Building Final (Inspection 153).
  - Review resources available to the construction team and go over any questions and answers.

**REQUIRED ITEMS DURING CALGREEN TIER 1 AND TIER 2 INSPECTION**

- The items that follow shall be complete at the time when Inspection 151 is scheduled to ensure that the CPA Building Inspector signs off the inspection card.
- Tier 1 Projects:
  - Storm water pollution prevention
  - Local storm water pollution prevention
  - Best management practices
  - Community connectivity
  - Brownfield or greyfield site redevelopment on infill area development (*Confirmation Required*)
  - Reduce development footprint and optimize open space (*Confirmation Required*)
  - Low impact development (LID) (*Confirmation Required*)
  - Greyfield or infill site (*Confirmation Required*)
  - Exterior noise transmission
  - Interior sound transmission
- Tier 2 Projects:  
(*In addition to any items shown under Tier 1 Projects*)
  - See list under Tier 1 Projects