

PLAN VIEW

Grate stake as manufactured by J.R. Partners

Tree as specified by City

KIVA model frame and grate as manufactured by Urban Accessories

3" perforated plastic flexible drain pipe with filter fabrics wrap. Finish pipe ends with perforated end caps or slotted grates.

PCC Curb and Gutter

Rootball

Don't disturb soil under rootball

Limits of excavation

SECTION A-A


Backfill with approved loam topsoil around root ball and water at time of planting.

NOTES:

1. Contact Underground Service Alert (USA) @811 or (800) 227-2600 at least five (5) days prior to beginning work to located existing utilities.
2. Soil, concrete and other materials spilled on street, sidewalk, and planting area shall be cleaned up immediately by Contractor.
3. If tree planting is delayed after tree wells are constructed, holes shall be filled and barricades secured to grates.
4. Provide minimum rootable soil volume for tree size growth performance (in cubic feet): Large: 1,200 cu.ft. Medium: 800 cu.ft. Small: 400 cu.ft.

| Rev | By | Date |
|-----|-----|----------|
| 0 | SGW | 12/14/92 |
| 1 | JT | 08/14/06 |
| 2 | HN | 03/19/07 |
| 3 | RTN | 06/11/17 |

Tree Well Details

Approved by: 

PE No. 72158

Date 01/10/18

City of Palo Alto Standard

Dwg No. 601

Scale: NTS